

To: 6 041305  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200-COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-19  
API NUMBER 15- 163-20,642-00-00

186K

NE SW NE, SEC. 29, T 9 S, R 20 W

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5845

Lease Name Lambert Well # 1

Operator: Chardel Oil Co.

County Rooks 128.53

Name & Address P.O. Drawer 368

Well Total Depth 3955 feet

Plainville, Kansas 67663

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 261 w/160 sz.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Plainville, Kansas 67663

Company to plug at: Hour: 9:30 A.M. Day: 19 Month: June Year: 19 91

Plugging proposal received from Delbert Ostrom

(company name) Chardel Oil Company (phone)

were: 5 1/2" casing set at 3954' w/150 sks. cement: perfs. at 3882' to 3955';

Perf. anhy. at 1800'; perf. base dakota at 1100'.

Ordered 350 sks. 60/40 poz. - 10% gel. w/1/4 lb. flocele plus 5 sks. hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:00 A.M. Day: 19 Month: June Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing w/25 sks. cement w/1/4 lb. flocele plus

pumped in add. 250 sks. cement w/1/4 lb. flocele and 400# hulls mixed in cement.

Max. 700 lb. S.I. 400 lb. Pumped in 8 5/8" casing w/75 sks. cement w/1/4 lb f.c.

and 100# hulls mixed in cement. Max. 700 lb. S.I. 500 lb.

RECEIVED  
STATE CORPORATION COMMISSION  
7-1-91  
JUL 01 1991

Remarks: (If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION Wichita, Kansas

INVOICED observe this plugging.

DATE JUL 19 1991

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 32325

6-19