

3-12
4-041355

195
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,761-00-00

SE SW SW /4 SEC. 13, 09 S, 19 W
330 feet from S section line
4290 feet from E section line

Operator license# 6931

Lease Hilgers well # 1

Operator: Bowman Oil Company

County Rooks

Address: Box 17
Codell, Kansas 67630

Well total depth 3591 feet 116.70
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 173 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Plainville, Kansas 67665

Company to plug at: Hour: 8:30A.M. Day: 12 Month: March Year: 92

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: _____

Were: 4 1/2" casing set @ 3590'. T.D. 3591'. Perf. @ 3230' - 3412'.
Anhy. - Perf. 1600'. Dakota @ 925'. W.L.M. 3350'. Top of fluid 3080'.
Order 300 sxs. 60/40 poz. - 10% gel. with 1/4# F.C. pluss 600# hulls.

RECEIVED
APR 11 1992
CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:00A.M. Day: 12 , Month: March , Year: 92

Actual plugging report: W.L.M. 3400'. Run in hole with perf. to perf.
anhy. @ 1600' and Base Dakota @ 925'. Hook up to 4 1/2" pumped in 255
sx. 60/40 pozmix - 10% gel. w/600# hulls mixed in cement. Max. P.S.I.
700#. S.I. 200#. Hooked-up to 8 5/8" S.P. Pumped in 20 sx. cement
w/500# P.S.I. Max. S.I. 500#

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I (and) did not [] observe the plugging.

Dennis L. Hamel

DATE 4-21-92

INV. NO. 34967

(agent)
Form CP-2/3

3-12