

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21107-00-00
SW-SE-NE, Sec. 11, T 9 S, R 20 W1/2
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5544

Lease Name ALLEN R Well # 1

Operator: THOMASON OIL COMPANY
Name & Address: 2700 OAK # A.
HAYS, KANS. 67601

County ROCK

Well Total Depth 2637 feet \$118.20

Conductor Pipe: Size 8 feet

Surface Casing: Size 8 7/8 feet 210

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEMENTING License Number _____

Address BOX 31 - 332 W. WICHITA, MO. RUSSELL, MO. 67665

Company to plug at: Hour: 11:00 AM Day: 14th Month: OCT Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO STEVE THOMASON

(company name) THOMASON OIL COMPANY (phone) 913-625-9045

were: 8 5/8" 210^{SK} SP. CML 11/150^{SK} CMT → 5 1/2" SET @ 2636 11/15^{SK} CMT
PACKER SET @ 3595^{SK} FT, PERFS. 3284^{SK} FT, 2340'-2355', 2512-31
ORDERED 400^{SK} 5/8^{SK} Formix 6% GEL-3% CA-CL, 6^{SK} HULLS.
5 1/2" PLUG, PUMP IN ANNULUS, AND 5 1/2" CSG. WITH PUMP TRUCK.
NO PIPE RECOVERY

Signed [Signature]
(TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 PM Day: 4th Month: OCT. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 400^{SK} 5/8^{SK} Formix 6% GEL-3% CA-CL, 6^{SK} HULLS. + 5 1/2" PLUG
PUMPED IN ANNULUS BETWEEN 8 5/8" AND 5 1/2" CSG 100^{SK} CMT 11/1^{SK} HULLS.
MIXED IN. PUMPED IN 5 1/2" CSG. 100^{SK} CMT. FOLLOWED BY
200^{SK} CMT. 11/4^{SK} HULLS. MIXED IN. MAX PRESSURE 400^{PSE}
MAX. PRESSURE IN ANNULUS. 400^{PSE} CEMENTED BY ALLIED CMT.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 11-2-83

INV. NO. 5973-6

RECEIVED
STATE CORPORATION COMMISSION
10/21/83
OCT 21 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN) BOIC