

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20932-00-00

Spot: S2SESE

Sec/Twnshp/Rge: 36-9S-20W

290 feet from S Section Line, 750 feet from E Section Line

Lease/Unit Name: PYWELL

Well Number: 1

County: ROOKS

Total Vertical Depth: 3812 feet

Operator License No.: 6931

Production Casing Size: 5.5 feet: 3806 w/125 sxs cmt

Op Name: BOWMAN OIL COMPANY

Surface Casing Size: 8.625 feet: 198 w/145 sxs cmt

Address: 805 CODELL RD.
CODELL, KS 67663

#123⁸⁹

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/11/2003 9:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: BILL BOWMAN

Company: BOWMAN OIL COMPANY

Phone: (785) 434-7206

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
Tubing sanded in hole. Fluid 300' from surface.
L-K Wireline ran line down backside to 965'.
Ran down 2 1/2" tubing to 1312'. Perforated 4 holes at 1300'.
Arbuckle open 3806' - 3812'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/11/2003 11:15 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Took injection rate 4 1/2 BPM 500# - found hole at 450' inside of tubing.
Allied pumped 120 sxs 60/40 pozmix - 10% gel down tubing - circulated cement.
Shut in tubing backside.
Allied pumped 215 sxs cement down tubing with 400# hulls scattered thru.
Max. P.S.I. 1000#. S.I.P. 800#.
Hooked up to 5 1/2" backside. Allied pumped 65 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 500#.
Note: Tubing left in hole - 0' - 3806'.

RECEIVED
JUL 16 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 7-16-03

INV. NO. 2004060070

Form CP-2/3

JUL 15 2003

LAWBANCO DRILG INC.
 NATOMA, KS 67651

#1 PYWELL

36-9-20W
 290' FSL &
 750' FEL, SE 1/4

CONTR CO. TOOLS

CTY ROOKS

GEOL JERRY GREEN

FIELD MARGOTTE

E 2245 KB CM 6/20/79 CARD ISSUED 9/15/79 IP P 12 BOPD

ARB OH 3806 1/2 -12

+	+	+	+

API 15-163-20,932

SMP	TOPS	DEPTH	DATUM
HEEB		3454	-1209
TOR		3476	-1231
LKC		3491	-1246
BKC		3724	-1479
ARB		3800	-1555
RTD		3812	-1567

8-5/8" 198/145sx, 5 1/2" 3806 1/2 /125sx

NO LOG

DST (1) 3516-33 (LANS C,D)/30-30-15-30,
 30' M W/SPKS O, SIP 873-800#, FP
 40-48/56-56#

DST (2) 3609-56 (LANS H,I)/30-45-60-45,
 270' MW, SIP 889-865#, FP 88-121/
 137-185#

DST (3) 3655-74 (LANS J)/13-15-15-15,
 15' M, SIP 24-70#, FP 24-24/32-32#

DST (4) 3742-3806 (CONG-ARB)/60-45-15-45
 10' OCM, 60' SOCM, SIP 169-161#,
 FP 48-48/56-56#

DST (5) 3741-3812 (CONG-ARB)/60-45-60-45
 135' VHO CM, SIP 1019-1011#, FP 88-
 96-121/129# (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS