

10-27

6 070871

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,124-00-00

NW SE NE, SEC. 28, T 9 S, R 20 W/E

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7973

Lease Name Mills Well # 1

Operator: Al La Lyn Oil Inc.

County Rooks 123.50

Name & Address 614 W. 10th

Well Total Depth 3800 feet

Ellis, Ks.

Conductor Pipe: Size 0 feet

Richard Romine

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 27 Month: Oct. Year: 19 90

Plugging proposal received from Bill Arys

(company name) Red Tiger Drilling (phone) 913-737-4260

were: 8 5/8 209 ft. s.p. cwc w/140 sks 60/40 poz 2% gel 3% ca cl. by Allied.

Abr. well - elev. 2262. Anhy 1747. No cir problems. vis 48. weight 9.5

Proposal 215 sks 60/40 poz 6% gel 1 sk f.c. Spot with drill stem. Circulate heavy

mud between all pugs. 25 sks at 3660. 25 sks at 1750. 100 sks w/1 sk f.c. at 1060.

40 ssk at 266. 10 sks at 40. 15 sks in rathole. circulate.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 1:15PM Day: 27 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Red Tiger ordered 215 sks 60/40 poz 6% gel and 8 5/8 plug. wiper

Spotted with drill stem, circ, heavy mud between all plugs.

- 1. 25 sks at 3660
- 2. 25 sks at 1750
- 3. 100 sks w/1 f.c. at 1060.
- 4. 40 sks at 266
- 5. 10 sks s.d. at 40
- 6. 15 sks in rathole cir. Cemented by Allied. Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-13-90

INV. NO. 29941

10-27

J.R.S.

Signed Marion J Schmidt (TECHNICIAN)

NOV 8-90