

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20644-00-02
Spot: W2SWSW Sec/Twnshp/Rge: 33-9S-20W
660 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: HINKHOUSE Well Number: 3
County: ROOKS Total Vertical Depth: 3835 feet

Operator License No.: 3258
Op Name: LANSING ENERGY OPERATIONS
Address: 107 N. MARKET, #1115
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3829
Surface Casing Size: 8.625 feet: 382 w/200 sxs cmt

3124.64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2003 10:00 AM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: ALAN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed Plugging Method: ****Mai Oil Operations is the operator and plugged this well.
Mai Oil Operations, Inc. filed a new lease which included this abandoned well.
Mai Oil Operations worked on the well and decided to P&A.
Emergency permission to plug this well with rig over the hole was given.
The address to invoice this pluggings is: #5259
Mai Oil Operatons, Inc. - 4514 Cole Ave., Suite 804 LB 30 - Dallas, Texas 75205.
*****Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Top of tubing fish 1255' w/rods inside. Fluid Level 300'.
Unable to get below 1255'.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/08/2003 12:45 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

ELI perforated Base Dakota 1160' - 2 shots. Bad pipe from 1186' to 1254'. Ran tubing to 1230'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel - circulated cement.
PTOH. Allied squeezed with 125 sxs cement with 400# hulls.
Max. P.S.I. 1000#. S.I.P. 700#.
Hooked up to backside.
Allied pumped 40 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED
MAY 14 2003
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS HINKHOUSE #1.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICAL)
INVOICED

DATE 5-14-03

Form CP-2/3

NO. NO. 2003061530

MAY 09 2003

BOWMAN OIL CO.
 P.O. BOX 17 #3 HINKHOUSE 33-9-20W
 CODELL, KS 67530 C W/2 SW SW
 CONTR RAINS & WILLIAMSON OIL CTY ROOKS

GEOL _____ FIELD MARCOTTE

E 2263 KB CM E8/15/81 CARD ISSUED 12/10/81 P 8 BO & 600 BWPD,

API 15-163-20,644A

ARB OH 3829-35

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
TOP		3291	-1028
HEEB		3494	-1231
TOR		3517	-1254
LKC		3538	-1275
B KC		3753	-1490
ARB		3832	-1569
RTD		3835	-1572
NO LOG			

OLD INFO: OPERATOR WAS TRUMART OIL,
 #1 HINKHOUSE, SPD 10/20/76, SET 8 5/8"
 382/200SX, COMPLETED AS D&A/ARB 10/
 27/76

- DST (1) 3584-3644/60, REC 1730' SW W/
 SC 0, SIP 992-952#, FP 238-740#
- DST (2) 3654-3735/120', REC 120' M,
 SIP 992-939#, FP 42-119#
- DST (3) 3811-3835/120, REC 210' OCSW
 (20% O) SIP 396-370#, FP 26-145#

NEW INFO: RE-ENTERED EST 8/15/81, WSH
 DWN, SET 5 1/2" 3829, MICT - CO, (ARB OH)
 SWB GSO, POP, P 8 BO & 600 BWPD 11/9/81

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS