

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20934-00-00
Spot: CW2NWNW Sec/Twnshp/Rge: 35-9S-20W
4620 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: PYWELL Well Number: 1
County: ROOKS Total Vertical Depth: 3900 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 207 w/150 sxs cmt
Production: Size 5.5 feet: 3899
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/07/2002 9:00 AM

Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC

Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
D.V. at 1680' set with 400 sxs.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/07/2002 4:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3800'. Mixed and pumped 150 sxs cement with 500# hulls.
Pulled up to 1600' and circulated cement with 110 sxs cement.
POOH. Swaged onto 5 1/2" and pumped 50 sxs cement.
Max. P.S.I. 1200#. S.I.P. 800#.
Hooked up to annulus and pumped 50 sxs cement.
S.I.P. 100#.


RECEIVED
OCT 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

J. B. COLLINS
 1007 CODY
 HAYS, KS 67601
 CONTR DREILING OIL, INC. #1 PYWELL
 CTY ROOKS 35-9-20W
 C W/2 NW NW

GEOL _____ FIELD NORTHAMPTON

E 2261 KB CM 6/23/79 CARD ISSUED 11/5/79 IP P 50 BOPD & 50 BWP
ARB 3836-3838

+	+	+
+	+	+
+	+	+

API 15-163-20,934

SMP	TOPS	DEPTH	DATUM
ANH		1726	+ 535
TOP		3271	-1010
HEEB		3474	-1213
TOR		3494	-1233
KC		3514	-1253
BKC		3732	-1471
CONG		3759	-1498
ARB		3814	-1553
RTD		3900	-1639

8-5/8" 207/150sx, 5 1/2" 3899

NO LOG TOPS REPORTED

NO DST'S
 MICT - CO, PF (ARB) 3836-3838, AC 500
 GAL, POP, P 50 BOPD & 50 BWP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

