

12-16-87
API NUMBER 15-163-03445-00-00

To: 6 040831
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SE, SEC. 35, T 9 S, R 20 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Wilson Well # C-10

Operator: Kaiser - Francis Oil Co.

County Rooks 121.23

Name & Address P.O. Box 666

Well Total Depth 3730 feet

Ellinwood, Ks. 67526

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 196' w/ 125 sx

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address Hays, Ks. 67601

Company to plug at: Hour: 9:00 AM Day: 16 Month: 12 Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser - Francis (phone) _____

were: 5 1/2" csg. set at 3730' with/150 sx ; Perfs at 3670-74; fish in hole, rods at 1500'
tbg. shot off at 1450'; Perf csg. at 1448' w/ 3 holes; perf. csg. at 950' w/ 3 holes
Ordered 200 sx, 65/35 poz, 10% gel, 2% lite, w/ 1/4 # flo-cele per sx. plus 5 sx hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 16 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT

Pumped in 5 1/2" csg. 25 sx cmt. w/ 1/4 # flocele plus 125 sx cmt w 1/4 # flocele and hulls.

Max P.S.I. 800# S.I. 400#

Pumped in 8 5/8" csg. 50 sx cmt. w/ 1/4 # flocele and hulls. Max 400 # 200 S.I. 300 #

Anhydrite At 1685 El. 2252

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE 1-11-88

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

INV. NO. 19484