

1-23

6 - 070984

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-3-7-54

SW SE NE / 4 SEC. 35, 09 S, 20 W
2970 feet from S section line
990 feet from E section line

Operator license# 6568

Lease Wilson C well # 4

Operator: Kaiser Francis Oil

County Rooks

Address: Box 21468
Tulsa, OK 74121-1468

Well total depth 3863 feet ^{125.54}
Conductor Pipe: 0 inch @ feet
Surface pipe 8 5/8 inch @ 214 feet

Aband. oil well xx, Gas well , Input well , SWD , D & A

Plugging contractor: B. J. Services License#

Address: Hays, Ks. 67601

Company to plug at: Hour: AM Day: 23 Month: Jan Year: 92

Plugging proposal received from: John Glenn

Company: Kaiser Francis phone: 918-494-0000

Were: 8 5/8 214 ft. s.p. cwc w/125 sks. 5 1/2 casing set at 3740 ft
w/150 sks cement. Perfs 3543 - 3548. Casing squeezed at 1172 sks cement.
Proposal 400 sks 60/40 poz 8% gel and 5 sks cement
Pump in w/pump truck. Load both 5 1/2 casing and 5 1/2 casing and
5 1/2 x 8 5/8 annulus w/cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All [x], Part [], None []

Completed: Hour: 11:30AM, Day: 23, Month: January, Year: 92

Actual plugging report: Kaiser Francis ordered 400 sks
60/40 poz 6% gel and 5 sks hulls pumped in w/pump truck. 1. Pumped
in 5 1/2 casing w/15 sks cement followed w/260 sks cement w/5 sks hulls
mixed in. Max pressure 600 psig. Shut in at 200 psig. 2. Squeezed
annulus w/125 sks cement. Max pres 250 psig. Shut in at (50) psig.
Cemented by B. J. Services Hays, Ks.

STATE CORPORATION COMMISSION
2-12-92
FEB 12 1992

Remarks:
Condition of casing(in hole): GOOD x BAD Anhy. plug: YES NO
Bottom plug(in place): YES x, CALC , NO Dakota plug: YES , NO
Plugged through TUBING x, CASING Elevation: GL

I observe the plugging.

INVOICED

DATE 2-17-92

INV. NO. 34575

Handwritten initials

Marion J. Schmidt
Marion J. Schmidt (agent)
Form CP-2/3