

6-2-87

6 030889

API NUMBER 15-065-21717-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 3, T 9 S, R 21 W/E
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6016

Lease Name Desbien Well # 1 SWD
County Graham 121.03

Operator: Condor Energy Inc.
Name & Address: Box 108
Great Bend, Kansas 67530

Well Total Depth 3724' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cmt. Co. License Number _____

Address Plainville, Ks.

Company to plug at: Hour: AM Day: 2 Month: June Year: 19 87

Plugging proposal received from Jim Davis

(company name) Condor Energy Inc. (phone) _____

were: 8 5/8" at 255' 5 1/2" at 3724'

Order 200 sks ATL 65/35 Poz 10% Gel 2% Dicol Allied Cmt. Co.

Sundowner Water Trucks.

DV Tool at 1629' w/400 sks.

Fluid level near bottom

Plugging Proposal Received by Carl Goodrow
Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 2 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Due to well being two staged through DV tool at 1629'

the casing was not perforated as per new opinion on cased holes.

Cmt. Co. tied on to 5 1/2" collar and squeezed with 200 sks ATL w/Max Psi. at 1500#.

Close in at 1500# Psi. Plug complete.

7/10/87
JUN 10 1987

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-15-87

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)

INV. NO. 17247