

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-21, 710-00-00

SW, Sec. 6, T 9 S, R 21 W/E

330 feet from N/S section line

1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6111

Lease Name SHIRLEY BASS Well # 1

Operator: N.-B. COMPANY INC.
Name &

County GRAHAM

Address BOX 506
RUSSELL, KANS.
67665

Well Total Depth 3855 feet

Conductor Pipe: Size 0 feet 0

Surface Casing: Size 8 5/8 feet 260'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor EMPHASIS OIL OP. License Number 624

Address BOX 506 - 4th RUSSELL, KANS. 67665

Company to plug at: Hour: 3:00 PM Day: 5th Month: NOV Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO DON FAVINGER

(company name) N-B-COMPANY INC (phone) 913-483-5345

were: 8 5/8" - 260' SB OUL w/150st COMMON - 2% GEL - 3% CA-CL.

ORDER - 200st 50/50 FORMIX 6% GEL AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 3840' w/20st CNT - 2nd PLUG @ 1800' w/20st CNT.

3rd PLUG @ 1020' w/100st CNT - 4th PLUG @ 270' w/40st CNT.

5th PLUG ^{SOLID BRIDGE} HALLS - PLUG @ 40' w/10st CNT Signed [Signature]
10st IN RAT HOLE (CIRCULARS) (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 PM Day: 5th Month: NOV Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 260' SB OUL w/150st (BY ALLIED CNT)

ORDERED 200st 50/50 FORMIX 6% GEL AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3840' w/20st CNT - 2nd PLUG @ 1800' w/20st CNT.

3rd PLUG @ 1020' w/100st CNT. 4th PLUG @ 270' w/40st CNT.

5th PLUG ^{SOLID BRIDGE} HALLS - PLUG @ 40' w/10st CNT. (10st IN RAT HOLE (CIRCULARS))

Remarks: CEMENTED BY ALLIED CNT.
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1982

NOV 22 1982

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I () / did not) observe this plugging.

INVOICED
DATE 12-27-82
INV. NO. 1942-W

Signed [Signature]
(TECHNICIAN)