

KANSAS

J

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11/2/66
NOV 2 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas Company

Complete Address: 580 Executive Terrace Bldg., 2809 Expressway Oklahoma City, Okla.,

Lease Name Harold Copeland Well No. 1

Location C SW SW SW Sec. 19 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3899

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4:30 P Day 31 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 3899' 8 5/8 csg set at 1740' cwc 800 sc

5 1/2 csg set at 3899' cw 200 sc cement.

PB 3790' Perf. 3550'

Pushed plug to 3500' Sandback to 3470'--Dumped 5 sc cem. with dump bailer.

Recovered 2695' of 5 1/2 csg.

Set plug and 20' rock bridge at 420'.

Filled to surface with 6 yds. readymix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. J. Messy*
Well Plugging Supervisor

INVOICED

DATE 11/2/66
INV. NO. 4223-u