

15-163-00247-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4/15/61
APR 15 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks
Location: CN 1/2 NE NE Sec. 20 Twp. 9 Rge. 20 (E) (W)
Name of Field: _____ Total Depth: 3865

I have this date completed supervision of plugging of:

Lease Name: Neil Well No. 1

Operator's Full Name: Frank J. Black

Complete Address: ~~1000 W~~ Box 150 Mc Pherson, Kansas

Plugging Contractor: R & D Casing Pulling Co

Address: Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7PM Day 24 Month 3 Year 61

The above well was plugged as follows:

10 3/4" 208' circulated with cement - 5 1/2" 3849' with 75 sax cement.
Filled with sand to 3830', set 4 sax cement with dump bailer, pulled
983' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (20 sax
Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 160',
displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.
Mudding and cementing By R & D Co pump truck.

Signed: *Edson Lewis*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 4/14/61
INV. NO. 2920-W