

11

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

W

FILE NO. _____

LOCATION NW-NW-NW

SEC. 20 TWP. 9 RGE. 20W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease J.W. Neil

Operator Palmer Oil Corp Address Union National Bank Bldg - Wichita

Field _____ County Proctor

Total Depth 3887 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 197 ft. cemented all around
10 sacks of cement on bottom of hole with Whump
Bailer - 3/4 in casing shot off at 1000 ft & pulled - hole
filled with mud - Plug set 200 ft & 15 sacks of cement
on top of Plug with Whump Bailer - Plug set 20 ft
below fluid surface with 10 sacks of cement on top
filling hole to surface - Plugged by Carroll Byers - Pipe
Pullers

C. M. Stough
District Conservation Agent

Date 6-10-1947

PLUGGING
FILE SEC 20 T 9 R 20W
BOOK PAGE 113 LINE 28

JUN 12 1947
6/12/47

11