

15-163-02218-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10/31/66
OCT 31 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas Company

Complete Address: 580 Executive Terrace Bldg., 2809 Expressway Oklahoma City, Okla.,

Lease Name Harold Copeland Well No. 4

Location C NE SW SW Sec. 19 Twp. 9 Rge. 20 (E) (W) x

County Rooks Total Depth 3941

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase Kansas License No. 436

Operation Completed: Hour 2 P Day 27 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 3941' 10 3/4" csg set at 238' cwc.

7" csg set at 3940' cw 175 sc cement. Plugged back to 3800.

5 1/2 csg set at 3800' Cemented but never completed.

Sand back to 3750' and dumped 7 sc cem. with dump bailer.

Recov. 2140' of 5 1/2 csg.

Recov. 720' of 7" csg.

Set 20' rock bridge at 310'

Filled to surface with 8 yds. readymix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/31/66
INV. NO. 4206-u