

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6/24/77  
JUN 24 1977  
CONSERVATION DIVISION  
WICHITA, KANSAS

R

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -163 -01731-00-30 (of this well)

Operator's Full Name Nadel & Gussman

Complete Address 3232 First National Tower, Tulsa, Oklahoma 74103

Lease Name Marcotte Well No. 2

Location C W/2 W/2 SW Sec. 26 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3812'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Allied Cementing Co.

Address        License No.       

Operation Completed: Hour 7 P Day 22 Month 6 Year 1977

The above well was plugged as follows:

Total Depth 3812' 8 5/8 csg set 171' cwc 100 sk.

5 1/2 csg set 3809' cw 100 sk cem.

5 1/2 csg PBDT 3025' Squeezed with 300 sk cem.

Cutoff 5 1/2 csg & welded steel plate on 8 5/8 csg W/2" opening.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls, followed with 150 sk 50-50 poz 6% gel & shutin.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey  
Well Plugging Supervisor

INVOICED

DATE 6-24-77

INV. NO. 5385-W