

15-163-01763-05-00

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
5/9/77  
MAY 09 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Nadel & Gussman

Complete Address 3232 First National Tower, Tulsa, Oklahoma 74103

Lease Name Marcotte Well No. 4

Location SW SW SW Sec. 26 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3829'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Allied Cementing Co.

Address        License No.       

Operation Completed: Hour 11 A Day 66 Month 5 Year 1977

The above well was plugged as follows:

Total Depth 3829' 10 3/4 csg set 124' cwc

7" csg set 3824' cw 150 sk cem.

7" csg sanded back (3829'-3792') No pipe recovered.

Cutoff 7" csg -welded steel plate W/2" opening on 10 3/4 csg.

Allied Cementing Co. mixed & pumped down 10 3/4 csg with 25 sk gel & water W/300 lbs

hulls -followed with 175 sk 50-50 poz 6% gel & shutin. PP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey  
Well Plugging Supervisor

INVOICED

DATE 5-9-77

INV. NO. 5113-W