

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
5/9/77  
MAY 09 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-163-01732-2002 (of this well)

Operator's Full Name Nadel & Gussman  
Complete Address 3232 First National Tower, Tulsa, Oklahoma 74103  
Lease Name Marcotte Well No. 3  
Location C E/2 W/2 SW Sec. 26 Twp. 9 Rge. (E) (W) 20  
County Rooks Total Depth 3884'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Co. Tools by Allied Cementing Co.  
Address        License No.         
Operation Completed: Hour 1 P Day 66 Month 5 Year 1977

The above well was plugged as follows:

Total Depth 3884' 8 5/8 csg set 124' cwc  
5 1/2 csg set 3883' cw 150 sx cem.  
5 1/2 csg sanded back (3884'-3775') 5 1/2 csg squeezed at 960' W/250 sk cem.  
No pipe recovered.  
Cutoff 5 1/2 csg. -welded steel plate W/2" opening on 8 5/8 csg.  
Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs  
hulls -followed with 150 sk 50-50 poz cem 6% gel & shutin. PP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 5-9-77

INV. NO. 5114-W