

API NUMBER None

LEASE NAME Gish C

WELL NUMBER 2

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 36 TWP. 9S RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 6-25-55

Plugging Commenced 5-7-85

Plugging Completed 5-7-85

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? --

Producing Formation None Depth to Top -- Bottom -- T.D. 3829

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| Arbuckle | Oil | 3825 | 29 | 8-5/8 | 190 | -0- |
| | | | | 5-1/2 | 3825 | -0- |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 40 sx cmt plug from 3829'-3457'. Gel plug from 3457'-1012'. Spotted 110 sxs cmt from 1012'-surf. Pumped 100 sxs cmt down csg annulus. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company

License No. 6568

Address P. O. Box 21468 Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa

Drew Tyler

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

P. O. Box 21468 Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 1985

Donna M. Knapp

Notary Public

My Commission Expires: 11-22-86

15-163-01795-00-00

COMPANY Francis Oil & Gas, Inc.

SEC. 36 T. 9 R. 20W
LOC. NW SW NW

FARM Gish C

NO. 2

TOTAL DEPTH 3829

COMM. 6/13/55

COMP. 6/26/55


SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

COUNTY Rooks

KANSAS



CASING

| | |
|----|---------|
| 20 | 10 |
| 15 | 8 195' |
| 12 | 6 |
| 13 | 5 3829' |

ELEVATION 2261 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|-----------------------------------|------|
| Surface clay & sandy shale | 60 |
| Shale & Shells | 195 |
| Shale | 770 |
| Sand | 830 |
| Shale | 920 |
| Shale with sand st. | 1066 |
| Shale & Shells | 1203 |
| Sand | 1400 |
| Shale & Shells | 1708 |
| Anhydrite | 1745 |
| Shale, Shells & Red Bed | 1975 |
| Shale & Shells | 2120 |
| Shale & Lime | 2490 |
| Shale & Lime with Streaks of Iron | 2595 |
| Shale & Lime | 3507 |
| Lime | 3543 |
| Shale & Lime | 3578 |
| Lime & Chert | 3621 |
| Lime | 3719 |
| Lime & Shale | 3770 |
| Lime, Shale & Chert | 3829 |

FORMATION TOPS

| | |
|------------------|------|
| HEEBNER | 3477 |
| TORONTO | 3498 |
| LANSING | 3516 |
| BASE KANSAS CITY | 3722 |
| ARBUCKLE | 3824 |

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By

[Signature]

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 29th day of June, 1955.

[Signature]
Notary Public

My commission expires February 13, 1956.