

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-21,747 717-000

LEASE NAME DESBIEN

WELL NUMBER # 1

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 9 RGE. 21 (W)

COUNTY GRAHAM

Date Well Completed 5-5-83

Plugging Commenced 6-2-87

Plugging Completed 6-2-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

**CONDOR ENERGY, INC.**

LEASE OPERATOR P. O. Box 108  
GREAT BEND, KANSAS 67530

PHONE# (316) 792-1751 OPERATORS LICENSE NO. 06016

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? HAYS, KANSAS

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation NONE - SWD Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3724'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>ARBUCKLE</u>	<u>WATER</u>	<u>0</u>	<u>255</u>	<u>8 7/8</u>	<u>255</u>	<u>0</u>
<u>3689-3725</u>		<u>0</u>	<u>3724</u>	<u>5 1/2</u>	<u>3724</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

FILLED HOLE WITH CEMENT FROM TOP TO BOTTOM WITH  
200 SKS CEMENT - DV TOOL AT 1629 WITH 400 SACKS CEMENT  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor CONDOR ENERGY, INC. License No. 06016

Address P.O. Box 108 - GREAT BEND, KANSAS 67530


STATE OF KANSAS COUNTY OF BARTON, ss.

Robert E. Davis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert E. Davis

(Address) Box 108, Gr. Bend, Kan 67530

SUBSCRIBED AND SWORN TO before me this 11<sup>th</sup> day of June, 1987



Notary Public H. D. Boyd

My Commission Expires: 8-3-89

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 14 1987  
 6/14/87  
 CONSERVATION DIVISION  
 Wichita, Kansas CP-4  
 Revised 08-84

17247

D & A OIL

3-9-21W  
NE NE NW

BOX 94


#1 DESBIEN

DAMAR, KS 67532

CONTR PIONEER DRILLING, INC. CTY GRAHAM

GEOLOGICAL \_\_\_\_\_ FIELD MOREL NORTH

ELV 2127 KB SPD 11/16/82 CARD ISSUED 5/5/83 IP TEMP ABD



API 15-065-21,717

LOG	Tops .....	Depth/Datum
SC	.....	2649- 522
TOP	.....	3072- 945
HEEB	.....	3287-1160
TOR	.....	3311-1184
LANS	.....	3328-1201
BKC	.....	3540-1413
MARM	.....	3579-1452
PENN-CONG	.....	3662-1535
ARB	.....	3689-1562
RTD	.....	3725-1598

8 5/8 " 255/140SX; 5 1/2 " 3724/100SX; DV TOOL AT 1629/400SX  
 DST (1) 3584-3645 (MARM) / 30-30-30-30, REC 15' M, SIP 74-63#, FP 31-31 / 36-36#  
 DST (2) 3622-83 (PENN-CONG) / 30-30-45-45, REC 20' OIL, 170' MCO, SIP 816-774#, FP 74-106 / 106-127#  
 MICT - CO, PF (CONG) 3662-65, 3668-72, W / 2 SPF, AC 1000G (7.5%), FRAC 10,000# SD & GEL WTR, POP, PMP ARB WTR, CHANNELED, OFF PMP, NON-COMMERCIAL, TEMP ABD, 3/10/83  
 - TO BE CONVERTED TO ARB SWDW AT A LATER DATE

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

NOTE: ORIGINALLY FIRST REPORTED IN NW NW NW

RECEIVED  
STATE CORPORATION COMMISSION

JUN 14 1987

CONSERVATION DIVISION  
Wichita, Kansas