

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 6 Twp. 9S Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner National Cooperative Refinery Association  
Lease Name McShann Well No. 1  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 7, 1955  
Application for plugging filed December 6, 1955  
Application for plugging approved December 7, 1955  
Plugging commenced January 18, 1956  
Plugging completed January 21, 1956  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3863 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	232'	None-cemented
				5 1/2"	3835'	3370'
				Hole was plugged back to 3662' & casing perforated from 3624' to 3627'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 3662' to 3610' and ran 4 sacks of cement. Mudded the hole with 70 barrels of mud to 232', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 35', set a rock bridge and ran 10 sacks of cement on top. Plugging completed.

Name of Plugging Contractor West Supply Company, Inc.  
Address Chase, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick  
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears (C. R. Sears)  
305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of January, 1956

My commission expires June 30, 1958.

RECEIVED  
STATE OF KANSAS  
Orville May  
1/28/56  
Notary Public

PLUGGING  
FILE SEC 6 T 9 R 21W  
BOOK PAGE 21 LINE 44

15-065-02312-00-00


KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY National Cooperative Refinery Association  
 FARM McShann NO. 1

SEC. 6 T. 9S R. 21W  
 LOC. SW SW SW

TOTAL DEPTH 3837'  
 COMM. 7/10/55 COMP. 7/26/55  
 SHOT OR TREATED  
 CONTRACTOR H-30, Inc.  
 ISSUED

COUNTY Graham  
 KANSAS



CASING  
 20 10  
 15 8 231'  
 12 6  
 13 5 3835'

ELEVATION 2270 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface clay, sand & Shale	25
Shale	805
Sand	855
Shale with sand streaks & Shells	1100
Sand	1195
Shale & Shells with sand streaks And Iron	1375
Shale & Shells & Red Bed	1770
Anhydrite	1820
Shale & Shells	1958
Shale, Shells & Red Bed	2185
Shale & Lime	2285
Shale, Lime & Salt	2400
Shale & Lime	3499
Lime	3510
Lime & Shale	3690
Lime, Shale & Chert	3803
Conglomerate & Chert	3803
Shale & Chert	3821
Lime & Chert	3837

FORMATION TOPS

TOPEKA	3242
HLEBNAR	3449
TORONTO	3475
LANSING	3493
CONGLOMERATE	3773
ARBUCKLE	3834

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By Merle Britting

STATE OF KANSAS |  
 COUNTY OF SEDGWICK | SS:

Subscribed and sworn to before me, a notary public, in and for said County and State this 28th day of July, 1955.

Gene Tusing  
 Notary Public

My Commission expires February 13, 1956.

PLUGGING  
 FILE SEC 6 T 9 R 21W  
 BOOK PAGE 21 LINE 44