

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 6 TWP. 9S RGE. 21 E/W  
Location as in quarters or footage from lines:  
C S/2 S/2 SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Windlawn Associates & N-B Company, Inc.  
Lease Name Shirley Buss Well No. 1  
Office Address 7395 Windlawn Way, Parker, CO 80134  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 11-05-82  
Application for plugging filed 11-05-82  
Plugging commenced 11-05-82  
Plugging completed 11-05-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Dry Hole  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Butcher  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3863'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	260'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

	Mud laden fluid @ 3863' - 3840'
RECEIVED	20 sks cement @ 3840'
STATE CORPORATION COMMISSION	20 sks cement @ 1800'
11/10/82	100 sks cement @ 1020'
NOV 10 1982	40 sks cement @ 270'
	10 sks cement @ 40'
CONSERVATION DIVISION	10 sks cement in rathole.
Wichita, Kansas	

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.  
Joe K. Branum (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum  
P. O. Box 506, Russell, KS 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 82



Glenda R. Tiffin  
Glenda R. Tiffin, Notary Public.

My Commission expires: February 6, 1984

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1982

CONSERVATION DIVISION  
Wichita, Kansas

EMPHASIS OIL OPERATIONS  
P. O. Box 506  
Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Windlawn Associates & N-B Company, Inc.  
7395 Windlawn Way  
Parker, CO 80134

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665

LEASE: Shirley Buss WELL: #1

LOCATION: C S/2 S/2 SW  
Section 6-9S-21W  
Graham County, Kansas

Total Depth: 3863'

Elevation: 2275' K.B.

Commenced: 10-29-82

Completed: 11-5-82

Casing: 8-5/8" @ 260' with 150 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	30'	Shale & Lime	1780'
Sand, Clay & Shale	265'	Anhydrite	1810'
Sand & Shale	1298'	Shale & Lime	2995'
Sand	1390'	Lime & Shale (L.T.D.)	3863'
Shale & Sand	1770'		

STATE OF KANSAS )  
                  ) ss:  
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

*Joe K. Branum*  
\_\_\_\_\_  
Joe K. Branum

Subscribed and sworn to before me this 8th day of November, 1982.

My Commission Expires: February 6, 1984.



*Glenda R. Tiffin*  
\_\_\_\_\_  
Notary Public