

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 35 Twp. 9S Rge. 20(W)

Location as "NE/CNW/SW" or footage from lines SW SE SW

Lease Owner Imperial Oil Company

Lease Name Marcotte Well No. 1

Office Address 780 Fourth Nat'l Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-20-61 19__

Application for plugging filed 10-20-61 19__

Application for plugging approved 10-20-61 19__

Plugging commenced 10-20-61 19__


Plugging completed 10-20-61 19__

Reason for abandonment of well or producing formation _____

No commercial quantities of oil found.

If a producing well is abandoned, date of last production -- 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3845' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	SURFACE CASING	-----		8-5/8"	191'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from -- feet to -- feet for each plug set.

Set first plug at 550 with 20 sacks cement;
Set second plug at 185 with 15 sacks cement;
Set top plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1961
10-30-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. A. Sladek (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William A. Sladek
780 Fourth Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 61

Bette J. Behrmer
Notary Public.

My commission expires July 27, 1964



15-163-00810-60-00
 RECEIVED
 OCT 30 1961
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLER'S LOG

Imperial Oil Company
 780 Fourth National Building
 Wichita 2, Kansas

Marcotte No. 1
 SW SE SW Sec. 35-9S-20W
 Rooks County, Kansas

Total Depth: 3845'

Elevation: 2241 K.B.
 Production: Dry

Commenced: 10-13-61 Completed: 10-21-61

Casing Record: Set 8-5/8" surface pipe at 189' with 150 sacks cement.

Figures indicate bottom of formations:

TOPS

Surface Shale & Sand	189'	Heebner	3485 (-1244)
Shale & Sand	1215'	Toronto	3504 (-1263)
Dakota Sand	1440'	Lansing	3526 (-1285)
Red Bed	1715'	Base Kansas City	3744 (-1503)
Anhydrite	1750'	Rotary Total Depth	3845 (-1604)
Shale & Shells	2130'		
Lime & Shale	2585'		
Lime	2870'		
Lime & Shale	3482'		
Lime	3537'		
Lime & Shale	3582'		
Lime	3845'		
Rotary Total Depth	3845'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond L. Bacon
 Raymond L. Bacon

Subscribed and sworn to before me this 26th day of October, 1961.

My Commission Expires:

July 27, 1964

Bette J. Behrmer
 Bette J. Behrmer, Notary Public