

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Rooks County, Sec. 35 Twp. 9 Rge. 20 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner I. O. Miller

Lease Name Pywell Well No. A-2

Office Address 619 Brown Building Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed 11-11-69 19\_\_

Application for plugging approved 11-12-69 19\_\_

Plugging commenced 12-8-69 19\_\_

Plugging completed 12-12-69 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3838 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	206	None
				5 1/2	None	619

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Rigged up pole. Set in jacks. Had 8" tension at 2500 psi.

Shot casing at 1500' - 1000' - 800' and 622'.

Pulled 20 joints of casing. Loading trailer. Tallied pipe.

Finished loading trailer. Tore rig down. Moved off location.

Allied squeezed well with 3 sacks of hulls - 15 sacks of mud and 100 sacks of 50-50 6% pozmix cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold


P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 22 day of December, 1969

My commission expires May 27, 1973

Notary Public.



Locate well correctly on above Section Plat

15-163-01783-00-00  
A-1-12


Well # 2 - SW NW NW Section 35-9-20 Rocks County, Kansas  
Company - I. O. Miller  
Contractor - Virginia Drilg. Co Inc.  
Commenced - August 26, 1953  
Completed Rotary Hole - September 6, 1953  
Elevation - 2270 DF  
Total Depth - 3838 (Rotary)

8 5/8" at 206  
5 1/2" at 3824

FORMATION	DEPTH
Shale	0- 206
Shale-sand	206-1210
Shale-sand-shells	1210-1640
Shale	1640-1730
Anhydrite	1730-1762
Shale-shells	1762-2185
Shale-lime	2185-2455
Shale	2455-2530
Shale-lime	2530-2780
Shale-shells	2780-3020
Shale-lime	3020-3140
Shale-shells	3140-3240
Shale-lime	3240-3395
Lime	3395-3496
Shale-lime	3496-3545
Lime	3545-3825
Conglomerate-lime	3825-3838 T. R. D.

TOPS:  
3487 - Heebner  
3507 - Toronto  
3525 - Lansing KO  
3833 - Arbuckle

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

  
S. A. Murphy

Subscribed and sworn to before me, a Notary Public,  
this 11<sup>th</sup> day of September, 1953.

  
Notary Public

My commission expires: Feb. 5, 1957.