


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rocks \_\_\_\_\_ County. Sec. 35 Twp. 25 Rge. (E) 20 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NE  
Lease Owner Francis Oil & Gas, Inc. - Veeder Supply & Dev. Co.  
Lease Name Wilson Well No. 1  
Office Address 905 Palace Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 29, 19.52  
Application for plugging filed March 29, 19.52  
Application for plugging approved March 29, 19.52  
Plugging commenced March 29, 19.52  
Plugging completed March 29, 19.52  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3860 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	227'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from 3860' to 170'. Set Plug with 15 sacks of cement. Heavy mud to 40'. Set plug at 40' with 10 sacks of cement.

4-8-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Veeder Supply & Development Company  
Address P. O. Box 201, Cherryvale, Kansas

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.  
FLOYD W. HILD

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEEDER SUPPLY & DEVELOPMENT COMPANY

(Signature) Floyd W. Hild

Box 201, Cherryvale, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of April, 19. 52


Lodes Lawson  
Notary Public.

My commission expires July 11, 1952

23-8390-s 6-51-20M

PLUGGING  
FILE SEC-35T 9 B 201  
BOOK PAGE 5 LINE 35

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis O. & G. - Veeder Supply Co. Farm Wilson No. 1 Depth 3860  
 Contractor Veeder Supply & Development Company Pipe Surface Hole 200' drilled and casing set when rotary moved in.  
 Location SW NW SE Sec. 35 Twp. 9S Range 20W  
 Commenced 3-15-52 Completed 3-29-52 County Rooks State Kansas

Surface Hole	0	200	200
Shale Sand	200	800	600
Shale	800	895	95
Sand	895	1020	125
Shale Sand	1020	1110	390
Shale Shells	1110	1590	180
Shale Shells	1590	2255	665
Lime Shale	2255	2520	265
Broken Lime	2520	2620	100
Lime	2620	2695	75
Lime Shale	2695	2775	80
Shale Lime Shells	2775	2910	135
Lime Shale	2910	3065	155
Shale Lime Shells	3065	3140	75
Lime	3140	3260	120
Lime Shale	3260	3320	60
Lime	3320	3760	440
Lime Conglomerate	3760	3805	45
Cherty Conglomerate	3805	3860	55
Total Depth	3860'		

Plugged at 170 feet with 15 sacks cement  
 Plugged at 40 feet with 10 sacks cement

AFFIDAVIT

STATE OF KANSAS  
 MONTGOMERY COUNTY SS:

FLOYD W. HILD, of lawful age, being duly and solemnly sworn on oath says; I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Wilson #1 Well in Section 35-9S-20W, Rooks County, Kansas, is true and correct.  
 Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

By Floyd W. Hild

Subscribed and sworn to before me this 31st day of March, 1952

Geo. Lawson  
 Notary Public

My Commission Expires July 11, 1952

**LOGGING**  
 FILE SEC 35 T 9 R 20W  
 BOOK PAGE 5 LINE 35

APR 18 1952  
 CONSERVED  
 Wichita, Kansas