

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Michelson of Dreiling Drlg. has this date requested permission to plug the following described well:

Mr. Michelson guarantees payment of the plugging fee.

Operator's full Name: Landes Exploration Co.

Complete Address: P.O. Box 867 Magnolia, Ark.

Lease Name: Moon Well No. 1

Location: NW SE SW Sec. 25 Twp. 9 Rge. (E)(W) 18

County: Rooks Total Depth 3660' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Michelson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base off cellar.

Very truly yours,

R. F. Messing
Conservation Division Agent