

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 6 1967
 2-6-67
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Tannitti of Woodman-Tannitti Drlg. has this
 date requested permission to plug the following described well:

Mr. Tannitti guarantees payment of the plugging fee.

Operator's full Name: W. F. Newton Et Al

Complete Address: Box 250 Conroe, Texas

Lease Name: Schrandt Well No. 1

Location: SE NW NE Sec 25 Twp. 9 Rge. 18 (E)(W) X

County Rooks Total Depth 3588' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Tannitti was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace
25 sc cement thru drill pipe. Heavy mud to 190' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Leo J. Massey
 Conservation Division Agent