

15-163-21796-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12/21/72
DEC 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Francis Oil & Gas, Inc.
Complete Address 4120 E. 51st St. Tulsa, Oklahoma 74135
Lease Name Gish "C" Well No. 3
Location C SW NW Sec. 36 Twp. 9 Rge. (E) (W) 20
County _____ Rocks _____ Total Depth 3817'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Co. Tools by Globe Cementing Co.
Address _____ License No. _____

Operation Completed: Hour 11 A Day 20 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3817' 8 5/8 csg set at 192' cwc 125 sx.
5 1/2 csg set at 3812' cw 125 sx cmt.
5 1/2 csg squeezed in 1958 W/200 sx at 1170' -1965 at 997 W/200 sx -hole developed at 1230' -set Lane Wells castiron plug at 3775'.
No pipe recovered.
Pumped down 5 1/2 csg with 200 lbs hulls & 5 sk gel & water -released 5 1/2 plug and pumped 70 sk cmt. PP 800 lbs. SI pres. 500 lbs.
Pumped down anulus with 30 sk cmt. 200 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massery
Well Plugging Supervisor

INVOICED

DATE 12/22/72
INV. NO. 6457-W