

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SW SE

SEC. 35 TWP. 9 RGE. 20

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. B-3 Lease Marcotte

Operator Lohmann - Johnson Address Evansville, Ind.

Field \_\_\_\_\_ County Rooks

Total Depth 3852 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 364' circulated with cement - 5 1/2" at 3850' with  
150 sax cement behind.

Filled with chat to 3845', set 4 sax cement with dump bailer,  
pulled 2920' 5 1/2" , filled with mud to 360', set rock and 10  
sax cement, mud to 35', set rock and 10 sax cement to bottom  
cellar.

**PLUGGING**  
FILE SEC 33 T 9 R 20  
BOOK PAGE 20 LINE 3

APPROVED  
STATE CORPORATION COMMISSION  
6/2/52  
JUN 2 - 1952  
CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
District Conservation Agent

Date 5-29-52