

15-163-01792-00-00

Form CP-3
Rev. 6-4-68

KANSAS

fl STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12/21/72
DEC 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Francis Oil & Gas, Inc.

Complete Address 4120 E. 51st St. Tulsa, Oklahoma 74135

Lease Name Gish "B" Well No. 3

Location NW NW SW Sec. 36 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3808'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co tools by Globe Cementing Co.

Address License No.

Operation Completed: Hour 1 P Day 20 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3808' 8 5/8 csg set at 205' cwc 135 sx.

5 1/2 csg set at 3803' cw 140 sx cmt.

5 1/2 csg squeezed in 1960 at 950' W/300 sx. Also squeezed in 1963 & 1966 cem unknown.

No pipe recovered.

Pumped down 5 1/2 csg with 25 sk cmt -400 lbs hulls & 35 sk gel & water-released

5 1/2 plug and pumped 70 sk cmt W/100 lbs hulls. PP 900 lbs. SI pres. 500 lbs.

Pumped 30 sk cmt down anulus with 200 lbs pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo P. Mansur
Well Plugging Supervisor

DATE 12/22/72

INV. NO. 6756-u