

15-163-01797-00-00

Form CP-3  
Rev. 6-4-68

*Handwritten mark*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4/2/70  
APR 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name White & Ellis Drilling, Inc.

Complete Address Box 448 El Dorado, Kansas 67042

Lease Name Pywell Well No. 1

Location SE SE SE Sec. 36 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3786

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pulling Inc.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 2:30P Day 30 Month 3 Year 1970

The above well was plugged as follows:

Total Depth 3786' 8 5/8 csg set at 235' cwc

5 1/2 csg set at 3775' cw 125 sk cmt.

5 1/2 csg top perf. (3651)

Filled 5 1/2 csg W/sd (3600-3786) Dumped 5 sk cmt W/dump bailer. (3560-3600)

Cutoff and recovered 1000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel - 70 sk cmt - 8 sk gel - plug and 50 sk cmt.

Gmt (0-200) Gel (200-520) Gmt (520-720) Gel (720-TD)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 4/2/70

INV. NO. 1671-W