

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

12/26/67  
DEC 26 1967

Operator's Full Name Fred Nixon & M. F. Bear

Complete Address Hillcrest Apt., Wichita, Ks.

Lease Name Pywell Well No. X 2

Location NW SE SE Sec. 36 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3825

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Ks. License No.       

Operation Completed: Hour 2:30 A Day 22 Month 12 Year 1967

The above well was plugged as follows:

RTD 3825' 8 5/8 csg set at 227' cwc 185 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem. thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 3 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Murray  
Well Plugging Supervisor

DATE 12/27/67  
INV. NO. 6974-W