

15-065-20543-0000

Form CP-3
Rev. 6-4-68

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

5/17/72

Operator's Full Name James W. Thompson,

Complete Address 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name Desbien Well No. 1

Location SE-NE-SW Sec. 3 Twp. 9 Rge. (E) (W)21

County Graham Total Depth 3702'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 10:30 AM Day 9 Month 5 Year 1972

The above well was plugged as follows:

282'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 110 Cu. Ft. cement
thru DP from 800' to 475'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Finkel
Well Plugging Supervisor

DATE 5/11/72
INV. NO. 5706-W