

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-15-69
DEC 15 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name I. O. Miller
Complete Address 619 Brown Bldg., Wichita, Kansas 67202
Lease Name Pywell Well No. A-2
Location SW NW NW Sec. 35 Twp. 9 Rge. (E) (W) 20
County Rooks Total Depth 3838
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Forbes Casing Pulling Co.
Address Box 221 Great Bend, Kansas License No. 149
Operation Completed: Hour 9:30A Day 12 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 3838' 8 5/8 csg set at 206' cwc
5 1/2 csg set at 383 1/4' cw 100 sk cmt.
Filled 5 1/2 csg W/sd (3800-3838) Dumped 5 sk cmt W/dump bailer. (3760-3800)
Dakato squeezed cutoff and recovered 600' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls, plug and 100 sk 50-50
poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/15/69
INV. NO. 1038-U

Signed: Leo F. Massey
Well Plugging Supervisor