

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 21-44

LOCATION SW SW SW

SEC. 6 TWP. 9 RGE. 21

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Mc Shann

Operator Natl Co-op Refg Address 305 Rule Bldg Wichita,

Field \_\_\_\_\_ County Graham

Total Depth 3839 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 232' circulated with cement - 5 1/2" cat 3835' with 100 sax  
cement behind - Lane Wells plugs to 3662' - perforated at 3624'.

Filled with sand to 3610', set 4 sax cement with dump bailer,

pulled 3336' 5 1/2" - filled with mud to 230', set rock and 15 sax  
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

*1/23/56*

*E. J. Perry*  
District Conservation Agent

Date 1-21-56

**PLUGGING**  
SEC. 6 TWP. 9 RGE. 21  
PAGE 21 LINE 44