

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. P. Nixon & Red Barron Productions, Incorporated.

Complete Address: 754 East Wichita Avenue, Russell, Kansas.

Lease Name Rouse Well No. 1

Location NW-NE-NW Sec. 6 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3748'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Shields Drilling Company, Incorporated.

Address: Shields Building, Russell, Kansas. License No. _____

Operation Completed: Hour 11:30AM Day 6 Month 6 Year 1969

The Above well was plugged as follows:

200'---8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 665'.

Circulated hole with heavy mud. Pulled DP to 890' and displaced 100 Sx. cement thru
DP from 890' to 565'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichol*
Well Plugging Supervisor

DATE 6/9/69
INV. NO. 9910-u