

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
8-26-68
AUG 26 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name American Petrofina Co. Of Texas

Complete Address: P. O. Box 209 Russell, Kansas 67665

Lease Name Allphin Well No. 1

Location NW SW NW Sec. 35 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3830'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 3 P Day 24 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 3830' 8 5/8 csg set at 241' cwc.

5 1/2 csg set at 3827' cw 100 sc cement.

Set sand bridge at 3100' and dumped 5 sx cement with dump bailer.

Recov. 800' of 5 1/2 csg.

Pumped thru 8 5/8 plg container with 20 sx gel W/5 sx hulls, 110 sx 50-50 poz cement

W/6% total gel, 5 sx galls, plug and 10 sx cement. Max Pres. 400 lbs. SI pres. 250 lbs.

Cmt (0-40) gel (40-240) Cmt (240-740) gel (740 to TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/26/68
INV. NO. 8340-4

Signed: Leo F. Massey
Well Plugging Supervisor