

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 055-21925-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Completion: 12-7-06

Well Operator: Kansas Natural Gas Operating, Inc. KCC License #: 32787

Address: P.O. Box 815 (Owner / Company Name) City: Sublette (Operator's)

State: Kansas Zip Code: 67877 Contact Phone: ( 620 ) 675 - 8185

Lease: Ohmes Well #: 2-A Sec. 23 Twp. 26 S. R. 32  East  West

NW - NW - NE - 1/4 Spot Location / QQQQ County: Finney

4950' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2440' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: None Set at: X Cemented with: X Sacks

Surface Casing Size: 8 5/8" - 24# Set at: 934' Cemented with: 425 SKS-Common-Lite Sacks

Production Casing Size: 5 1/2" - 15.5# Set at: 2737' Cemented with: 425 SKS-Life & 125 SKS "C" Sacks

List (ALL) Perforations and Bridgeplug Sets: 2692' - 2702' KB, 2716' - 2724' KB, (4) Shots per Foot

(72 Total Holes)

Elevation: 2901' ( G.L. /  K.B.) T.D.: 2740' KB P.B.T.D.: 2737' KB Anhydrite Depth: Bottom at 1983'

(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Hook onto 5 1/2" casing & bullhead, approx. 280 sacks of 60-40 Poz mix cement & 6% gel mixed w/500# of cottonseed hulls to load casing w/cement. Hook onto backside & attempt to check annulus. Cut wellhead off 6' below ground. Recommendation by Mr. Michael Maier from KCC in Dodge City.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? We were awaiting a couple of flow tests on well to decide whether to keep well or plug to abandon. Have now decided to plug well. Please find ACO-1 Form attached to this Plugging Application.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Steve Lehning, Supt.

For Kansas Natural Gas Operating, Inc. Phone: ( 620 ) 675 - 8185

Address: P.O. Box 815 City / State: Sublette, KS 67877

Plugging Contractor: Halliburton KCC License #: 5287 999917

Address: Liberal, Kansas (Company Name) Phone: ( 800 ) 853 - 3555 (Contractor's)

Proposed Date and Hour of Plugging (if known?): As soon as KCC approves Plugging Procedure.

RECEIVED

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

APR 23 2007

Date: 4-23-07 Authorized Operator / Agent: Steve Lehning, Supt.

(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Kansas Natural Gas Operating, Inc.  
PO Box 818  
1200 Main Street  
Hays, KS 67601

April 24, 2007

Re: OHMES #2-A  
API 15-055-21925-00-00  
NWNWNE 23-26S-32W, 4950 FSL 2440 FEL  
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

Barry Metz  
Deputy Director

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888