

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 081-20899 -00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334
(Owner / Company Name) (Operator's)
Address: P.O. Box 18596 City: Oklahoma City
State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 879 - 9375
Lease: MLP Rooney Well #: 1-5 Sec. 5 Twp. 30 S. R. 34 East West
- - NE - SE Spot Location / QQQQ County: Haskell

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1,805' Cemented with: 675 Sacks
Production Casing Size: 5 1/2" Set at: 5,728' w/ port collar @ 3,069' Cemented with: 275 sacks & (port collar - 500 sacks) Sacks
List (ALL) Perforations and Bridgeplug Sets: 5,631' - 5,638' (2 spf), 5,476' - 5,481' (2 spf), Bridge Plug @ 5,350', 5,295' - 5,304' (4 spf)

Elevation: 2,992' (G.L. / K.B.) T.D.: 5,820' PBDT: 5,728' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole
Proposed Method of Plugging (attach a separate page if additional space is needed): MIRU cementers, dig out bradenhead, pump 400# cotton seed hulls, pump 110 sx cmt, wait 20 min, top off with mud if needed, tie onto 5 1/2" x 8 5/8" annulus, attempt to est. pump in, if able pump into annulus, mix and pump 50 sx cmt, RDMO cementers, weld on cap, clean up location.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No
If not explain why? _____

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 07 2007

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Conservation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____
Bud Neff Phone: (620) 277 - 0803
Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846
Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)
Address: _____ Phone: () -

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 5/3/07 Authorized Operator / Agent: Altha Dewby King For Doug Haweth
(Signature) Asset mgr.

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Chesapeake Operating, Inc.
PO Box 18496
6200 N Western Ave.
Oklahoma City, OK 73154-0496

May 09, 2007

Re: MLP Rooney #1-5
API 15-081-20899-00-01
NESE 5-30S-34W, 1980 FSL 660 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely

Barry Metz
Deputy Director

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888