

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 081-21286 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/5/2000

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334

Address: P.O. Box 18496 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 879 - 9375

Lease: MLP Rooney Well #: 4-5 Sec. 5 Twp. 30S S. R. 34 East West

SW - NW - NE Spot Location / QQQQ County: Haskell

1250 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2100 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 1855' Cemented with: 650 Sacks

Production Casing Size: 5-1/2 Set at: 5700' & port collar @ 3,138' Cemented with: 300 & 425 sacks (port collar) Sacks

List (ALL) Perforations and Bridgeplug Sets: 5,621' - 5,631' (2 spf), 5,478' - 5,494' (2 spf), bridge plug @ 5,370', 5,306' - 5,310' (2 spf), 5,299' - 5,303' (2 spf)

Elevation: 2999 (G.L. / K.B.) T.D.: 5700 PBTD: _____ Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): MIRU WOU, MIRU Cementers, dig out bradenhead, pump 300# cotton seed hulls,

pump 100# CS hulls + 25 sx cmt. Pump 50 bbl mud spacer, pump 100 sx cmt, wait 30 minutes, top off with mud if necessary. Tie onto

5-1/2x8-5/8 annulus, attempt to establish pump in. If able, pump into annulus. Pump 50 sx cmt. RDMO cementers. Weld on cap & clean up location.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Logs filed with ACO-1.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 07 2007

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Bud Neff CONSERVATION DIVISION WICHITA, KS

Phone: (620) 277 - 0803

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/3/07 Authorized Operator / Agent: Alotha Devore-King for Doug Hawthth (Signature) ASSET mgr.

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



Aletha M. Dewbre-King
Regulatory Analyst

May 3, 2007

VIA UNITED PARCEL SERVICE

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

Re: MLP Rooney 4-5
5-30S-34W
Haskell Co., KS
API #15-081-21286

MLP Rooney 1-5
5-30S-34W
Haskell Co., KS
API #15-081-20899

Dear Sir or Madam:

Enclosed are CP-1 forms for the referenced wells.

If additional information is required, please contact me at (405) 767-4775 or by e-mail at: adewbre-king@chkenergy.com.

Sincerely,

Aletha M. Dewbre-King
Regulatory Analyst

Enclosures

xc (via e-mail): Kansas Plugging Distribution List

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 07 2007

CONSERVATION DIVISION
WICHITA, KS

W:\RegOps\State_Regulatory_Permitting\Regulatory KS\~ks\CP-1 (Well Plugging App)\Correspondence\2007\MLP Rooney 4-5, & 1-5 (2 apps).doc



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Chesapeake Operating, Inc.
PO Box 18496
6200 N Western Ave.
Oklahoma City, OK 73154-0496

May 09, 2007

Re: MLP ROONEY #4-5
API 15-081-21286-00-00
SWNWN 5-30S-34W, 1250 FNL 2100 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely

Barry Metz
Deputy Director