

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07244-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 3-14S-15W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: FOSTER W T Well #: 8-B
County: RUSSELL Total Vertical Depth: 3309 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------------|
| PROD | 7 | 3052 | 0 | w/unknown sxs cmt |
| SURF | 10.75 | 930 | 0 | w/unknown sxs cmt |

\$ 107.54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2007 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2725

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2007 1:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Well had been squeezed at 990' w/250 sxs and 508' w/125 sxs.
Ran tubing to 2820'.
Pumped 25 sxs gel with 100# hulls, followed with 60 sxs common cement with 100# hulls.
Pulled to 1000' - circulated with 135 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
POOH. Topped off with 15 sxs.
Tied onto backside and pumped 75 sxs cement.
Max. P.S.I. 150#. Cement circulated up outside of surface pipe.

INVOICED
DATE 5-8-07
INV. NO. 2007061717

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100.

Signed _____

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-273

MAY 07 2007

CONSERVATION DIVISION
WICHITA, KS

MAY 04 2007

RM