

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-07044-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 36-19S-12W  
850 feet from S Section Line, 5114 feet from E Section Line  
Lease Name: BIRZER FLORA Well #: 1  
County: BARTON Total Vertical Depth: 3353 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S. YALE #702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3348	0	150 SX CMT
SURF	8.625	160	0	150 SX CMT

\$ 108.97

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/03/2007 12:00 PM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed  
Plugging  
Method:

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/03/2007 3:30 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Had tried to get down well several times in the past year. Always encountered junk/casing/iron sulfide at about 300' with power swivel-wash over pipe, etc. Got down to 535' on last attempt. Ran tubing to 502' - circulated with 75 sxs 60/40 pozmix - 10% gel cement. Packed off tubing head. Circulated up backside with 125 sxs cement. POOH. Tied onto casing and pumped 25 sxs cement. Max. P.S.I. 300#. S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
3350	3353		
3138	3146		
3127	3130		
3110	3116		
3085	3092		
2884	2889		

INVOICED

DATE 5-8-07  
INV. NO. 2007061718

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*AD*

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 07 2007

CONSERVATION DIVISION  
WICHITA, KS

MAY 04 2007

*CSG*

W. L. HARTMAN

#1

FLORA BIRZER

36-19-12W  
NW SW SW

Contr.

BARTON

County

E. 1802RB

Comm.

Comp.

2-19-54

IP

25 BOPD

Tops	Depth	Datum
TOP	2704	-902
HEEB	2946	-1174
B/OREAD	2976	-1174
BR LM	3066	-1264
LANS	3083	-1281
B/KC	3326	-1524
CONG	3335	-1533
ARB	3346	-1544
TD	3350	-1548


Casing

8" 160

5" 3348

CO 3350

HAMMER POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS