

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24363-00-00
Spot: NESWSE Sec/Twnshp/Rge: 11-20S-26W
1150 feet from S Section Line, 1450 feet from E Section Line
Lease Name: JAMES Well #: 1
County: NESS Total Vertical Depth: 4531 feet

Operator License No.: 5146
Op Name: RAINS & WILLIAMSON OIL CO., INC.
Address: 220 WEST DOUGLAS, STE 110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1835		WITH 425 SX CMT
PROD	4.5	4516	0	WITH 150 SX CMT \$ 147.26
SURF	8.625	214		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2007 10:30 AM
Plug Co. License No.: 5146 Plug Co. Name: RAINS & WILLIAMSON OIL CO., INC.
Proposal Rcvd. from: CLAUDE BLAKESLEY Company: RAINS & WILLIAMSON Phone: (620) 663-1845

Proposed Plugging Method: PUMP 30 SX CMT & 150# HULLS. PUMP GEL SPACER TO 1800'. PUMP CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2007 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:


TIE ONTO CASING & PUMP 30 SX CMT WITH 150# HULLS TO BOTTOM. PUMP 14 SX GEL SPACER TO 1800'. CMT TO SURFACE WITH 210 SX CMT. CHECKED BACKSIDE WITH 10 SX CMT.

INVOICED
DATE 5-8-07
INV. NO. 2007061725

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 07 2007

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION

APR 27 2007

CONSERVATION DIVISION
WICHITA, KS

Form CI-23