

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20463-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 27-4S-22W  
990 feet from S Section Line, 330 feet from W Section Line  
Lease Name: WARREN Well #: 1  
County: NORTON Total Vertical Depth: 3706 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		

\$ 120.45

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2007 6:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.  
Arbuckle tested and recovered 6' mud - no plug.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE  
Date/Time Plugging Completed: 04/25/2007 9:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1900' w/25 sxs.  
2nd. Plug at 1175' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Perfs:

INVOICED  
DATE 5-4-07  
INV. NO. 2007061707

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 03 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

APR 30 2007

PLG