

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05736-00-01

Spot: S2S2SE

Sec/Twnshp/Rge: 32-15S-12W

330 feet from S Section Line, 1320 feet from E Section Line

Lease Name: HILGENBERG A NWBU Well #: 2 1-1 *ka*

County: RUSSELL

Total Vertical Depth: 3259 feet *apb 5-18-07*

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3256	0	w/unknown sxs cmt
SURF	8.625	349	0	w/unknown sxs cmt

\$105.92

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/26/2007 10:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: BOB GRANT

Company: BEREXCO, INC.

Phone: (785) 625-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/27/2007 3:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

CIBP at 3210' - 3070' - 3015'.
Cut off casing at 1550'.
Pulled to 1415' - pumped 140 sxs 60/40 pozmix - 10% gel w/200# hulls.
Pulled to 774' - pumped 25 sxs cement.
Pulled to 647' - pumped 25 sxs cement.
Pulled to 422' - circulated w/120 sxs cement with 400# hulls.
Topped off with 15 sxs cement.

INVOICED
DATE 5-8-07
INV. NO. 2007061716

Remarks: LEASE RE-NAMED NW BEAVER UNIT #1-1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 07 2007

CONSERVATION DIVISION
WICHITA, KS

APR 23 2007

N.C.R.A. #2 HILGENBERG 'A' 'OWW0' 32-15-12W
 CONTR UNKNOWN CTY RUSSELL C S/2 S/2 SE
 GEOL FIELD HALL-GURNEY
 ELV 1813 KB SPD E1/1/52 CARD ISSUED 3/26/87 # P 24.96 BO & 7.04 BWPD
 LKC 2994-3003

API NOT ASSIGNED

SMP	Top	Depth/Datum
ANH	755	+ 1058
HEEB	2892	-1079
TOR	2912	-1099
BR LM	2979	-1166
LANS	2990	-1177
GORHAM	3255	-1442
ORTD	3259	-1446

OLD INFO: OPERATOR WAS SAME, #2 HILGENBERG, SPD 2/13/50, SET 8 5/8 " 349, 5 1/2 " 3256, COMP AS P 48 BO & 7 BWPD, LKC 2994-3003 OA (CARD ISSUED 4/14/50), CONTR: M. B. ARMER

NO CORES OR DSTS
 MICT - CO TO ORTD, DRLD PLUG AT 3259, TST WTR, PB 3150, PF (LKC) 48 / 3075-3082, SO & WTR, SQZ'D PFS W / CMT, PB 3072, PF (LKC) 3060-3068, AC 500 GAL, SWB ALL WTR, PB 3050, PF (LKC) 3024-3027, 3020-3024, 3003-3005, 2992-2996, CO TO 3069, SWB ALL WTR, SQZ'D PFS W / CMT, CO CMT, PF (LKC) 3020-3027, SWB WTR, PF (LKC) 3001-3003, 2994-2997, AC 1500 GAL, SO, POP, P 5 BOPH & 30% WTR / 24 HRS, P 48 BO & 7 BW / 24 HRS

NEW INFO: PROD DECL TO 8 BO & 1.14 BWPD, REWORKED E 1/1/52, MICT - CO, PB 3017, SWB 16.88 BF (88% OIL) / 11 HRS, BAIL 92.34 GO & 77.52 GW / 2.5 HRS, PB 2960, PF (TOR) 34 / 2913-2919, TST 3 GO & TR WTR / 2 HRS, AC 500 GAL, SWB 4.27 BF (90% OIL) / 2 HRS, FU 150' FL / 30 HRS, SWB 2.18 BFPH / 6 HRS, CO TO 2919, SWB 9.46 BF / 3 HRS, SWB 2.5

(over)

COPYRIGHT 1987
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS