

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05962-00-01  
Spot: SEWNNE Sec/Twnshp/Rge: 28-11S-17W  
4285 feet from S Section Line, 1679 feet from E Section Line  
Lease Name: BEMIS A Well #: 13  
County: ELLIS Total Vertical Depth: 3898 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 1658 COLE BLVD., STE 205  
LAKEWOOD, CO 80401

| String | Size  | Depth (ft) | Pulled (ft) | Comment           |
|--------|-------|------------|-------------|-------------------|
| COND   | 16    | 31         |             |                   |
| L1     | 5.188 | 3600       |             |                   |
| PROD   | 7     | 3393       | 0           | w/unknown sxs cmt |
| SURF   | 10.75 | 1110       | 0           | w/unknown sxs cmt |

Well Type: SWD UIC Docket No: D00351.0 Date/Time to Plug: 05/03/2007 1:50 PM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: SHELBY RESOURCES LLC Phone: (303) 274-4682

Proposed Plugging Method: 4" cement lined tubing - shoot at 1825' - salt section.  
Run 2 7/8" tubing to 3886' - pump 100 sxs common cement with 3% cc.  
Pull tubing to 2500' - clear tubing. Pull to 1800' - stop for 1-2 hours.  
Pull to 1500' - pump 100 sxs common cement with 3% cc.  
Pull to 700' - pump 100 sxs common cement with 3% cc - wait for hole to circulate.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/03/2007 3:26 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Shot 4" cement lined tubing to 1825'.  
Ran 2 7/8" tubing to 3886' - pumped 100 sxs common with 3% cc.  
Pulled to 2500' and cleared 2 7/8" tubing.  
Pulled to 1800' - pumped 30 sxs common with 3% cc - cleared and 70 sxs common with 3% cc and 200# hulls.  
Operator decided not to stop - got return circulation.  
Pumped another 100 sxs common with 3% cc with 200# hulls.  
Got cement return.

Perfs:

INVOICED  
DATE 5-14-07  
INV. NO. 2007061744

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 11 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04


Signed Bruce Basye  
(TECHNICIAN)

MAY 09 2007

THE TEXAS CO #A-13 BEMIS 28-11-17W  
 SE NW NE  
 Contr. \_\_\_\_\_  
 E. 1893 Comm. 9-3-37 Comp. 9-30-37 IP \_\_\_\_\_ S W D W  
 4290 FSL  
 16 S FEL  
 County

| Tops | Depth | Datum |
|------|-------|-------|
|      |       |       |
|      |       |       |
|      |       |       |
|      |       |       |
|      |       |       |
|      |       |       |
| ARB  | 3393  |       |
| REAG | 3875  |       |
| GRAN | 3925  |       |
|      |       |       |
| TD   | 3926  |       |

Casing  
 10" 1103  
 7" 3393  
 3100' OIH/2 hrs  
 OWDD: 8-28-39  
 OTD 3400  
 DD TO 3926  
 SWDW: Input 175 BWPB



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS