

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01391-00-00
Spot: NENENW Sec/Twnshp/Rge: 36-12S-22W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 11-7
County: TREGO Total Vertical Depth: 4052 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4030	0	175 SX
SURF	8.625	495	0	325 SX

\$ 131.69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/03/2007 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 430 sxs 60/40 pozmix - 10% gel - 800# hulls.
Perf Tech perfed at 550' - 980' - 1820' - 2350'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/03/2007 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

D.S.& W. RIH with tubing to 3875'. Copeland rigged to tubing - pumped 110 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 2500'. Copeland rigged to tubing - pumped 110 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 1000'. Copeland rigged to tubing - pumped 80 sxs 60/40 pozmix with 150# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing - pumped 20 sxs 60/40 pozmix.
Max. P.S.I. 350#. S.I.P. 350#.
Rigged to 8 5/8" casing - pumped 5 sxs 60/40 pozmix.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4026	4028		
3996	4004		

INVOICED
DATE 5-8-07
INV. NO. 2007061727

Remarks: LEASE ORIGINALLY KNOWN AS SCOTT #7. COPELAND CEMENTING & ACID-TICKET #C0439148.

Plugged through: TBG

District: 04

Signed [Signature]

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

MAY 07 2007

CONSERVATION DIVISION
WICHITA, KS

MAY 04 2007

TEXAS COMPANY

#7

SCOTT

36-12-22W
NE NE NW

Contr. POWELL DRILLING COMPANY

TREGO

County

E 2344

Comm.

Comp.

6-13-52


IP 101 BOPD (ARB)

PHY BOT

Tops	Depth	Datum
ANH	1744	600
TOP	3377	-1033
HEEB	3576	-1232
LANS	3608	-1264
ARB	3996	-1652
T D	4052	-1708

Casing

8" 495 CO 4028; PERF 24 S,
5" 4030 4012-26; ACID 500;
SWB 2 BOPH; ACID
200; DD 4052; SWB
2 BOPH & 15 GWPB;
PB 4006; PERF 29 S,
3996-4004; ACID
500; CO 4052; SWB
2 BO & 4 BWPB; PERF
OGALLAH POOL PERF 7 S, 4026-
28



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS