

3 023154

To:

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER N/A 15-001-⁰²³²¹~~0231~~-00-00

NW SW, SW, SW 1/4 Sec/Twp/Rge S.22-T.26S.-R.18E.

495 feet from south section line

5001 feet from east section line **\$ 35.00**

TECHNICIAN'S PLUGGING REPORT

Operator License # 1005488

Lease/Well# DICE NO.013

County ALLEN

Operator: TWM PRODUCTION CO.

Well Total Depth 800' feet

Name & 1150 HWY 39

Production Pipe: 2" Size Feet 800

Address CHANUTE, KS. 66720

Surface Casing: 8" Size Feet 40'

AB oil well X Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: W & W PRODUCTION CO. Lic. # 5491

Address: 1150 HWY 39, CHANUTE, KS. 66720

Company to plug at: Hour: 1:00PM Day: 21 Month: 2 2007

Plugging proposal received from: MIKE WIMSETT

Company Name: W & W PRODUCTION CO. Phone: 620-431-4137

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT MAY HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PERFORATE THE CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part **TECHNICIAN**
None **X**

Operations Completed: Hour: 4:00P.M. Day: 19 Month: 4 2007

Actual Plugging Report: THE 2" CASING WAS PEFORATED AT 500' AND WAS PERFORATED AT 200'. 1" PIPE WAS RAN INTO THE 2" CASING TO 830'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE.THE 1" PIPE WAS REMOVED. THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2" CASING. CEMENT WAS SQUEEZED INTO THE WELL TO 800 PSI AND THE WELL WAS SHUT IN. 42 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

INVOICED

Remarks: (SPOT LOCTION ESTABLISHED BY GPS AS DIC 01)
(If additional description is necessary, use BACK of this form.)

DATE 5-9-07
INV. NO. 2007061730

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Handwritten initials