

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01913-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 11-10S-25W
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: EAST ELRICK Well #: 1-1
County: GRAHAM Total Vertical Depth: 4205 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 221 S. BROADWAY, STE. 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3980	0	w/150 sxs cmt
RBP		3960		
SURF	8.625	170	0	w/140 sxs cmt

\$ 136.60

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2007 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY, INC. Phone: (785) 623-4081

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 600# hulls.
PBTD 3960'. Well has casing leaks - high fluid level.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2007 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2711'.
Allied Rigged to tubing and pumped 50 sxs 60/40 pozmix neat - followed with 100 sxs 60/40 pozmix with 400# hulls mixed in.
Pulled tubing to 2000'. Allied rigged to tubing and pumped 40 sxs cement with 150# hulls to circulate cement into pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 20 sxs - found hole on top of wellhead.
Rigged to 8 5/8" casing - pumped 10 sxs cement - also blew out of hole on top of wellhead.
Hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3950	3953		
3928	3931		
3908	3917		
3887	3891		
3825	3829		
3818	3821		
3791	3798		
3744	3750		

INVOICED

DATE 5-11-07
INV. NO. 2007061737


RECEIVED
KANSAS CORPORATION COMMISSION
MAY 10 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: LEASE ORIGINALLY KNOWN AS ROME #1. ALLIED CEMENTING COMPANY-TICKET #32957.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

MAY 08 2007

Handwritten initials

D. G. HANSEN

#1

ROME

11-10-25W
SW NW NW

Contr. C-G DRILLING

GRAHAM

County

E. 2473 RB

Comm.

Comp. 10-14-60

IP 125 BOPD

Tops	Depth	Datum
ANH	2114	+359
HEEB	3718	-1245
TOR	3738	-1265
LANS	3756	-1283
B/KC	3987	-1514
CHERO SH	4176	-1703
CHERO LM	4186	-1713
TD	4205	-1732

Casing
8" 170
5" 3977
DST 3725-50/30", 4' M, BHP 0//
DST 3789-3805/90", 250' G, 25' WTRY OILY
M, 120' MDY W, BHP 1260-1140//
DST 3881-3900/30", 8' M, BHP 110-0//
DST 3900-22/90", 1100' G, 40' OCM, 30'
H OCM, 30' MDY O, 60' FROGGY O, BHP
1155-1050//
DST 3920-45/30", 9' M, W F SPKS O, BHP
970-0//
DST 3945-67/30", 20' V SL OCM, BHP 945-0//
ELRICK POOL DST 4188-4205/30", 10' M
BHP 0//: PERF 24/3908-12: 24/
3911-17: 18 GOPH: ACID 500:
3 1/2 BOPH: REACID 1500: 4 1/2 BOPH

+	+	+
+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS