

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19134-00-00
Spot: N2NESE Sec/Twnshp/Rge: 32-13S-15W
2240 feet from S Section Line, 660 feet from E Section Line
Lease Name: MERMIS C Well #: O-37
County: RUSSELL Total Vertical Depth: 3320 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3322	0	w/250 sxs cmt
SURF	8.625	239	0	w/150 sxs cmt

\$ 107.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2007 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2725

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix- 10% gel - 600# hulls.
BP at 3130'. Junk in the hole at 1150'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2007 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RTI to 1150' - pumped 100 sxs cement - good circulation.
Pulled tubing - tied onto 5 1/2" - squeezed 30 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
Tied onto backside - squeezed 15 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
No hulls.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 10 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 5-11-07
INV. NO. 2007061739

Remarks: ALLIED CEMENTING COMPANY-TICKET #21184.

Plugged through: TBG

District: 04

Signed Marvin Mills

(TECHNICIAN)

Form CP-2/3

MAY 07 2007